

KERALA MEDICAL SERVICES CORPORATION LTD.

(A Govt. of Kerala, Undertaking)

Thycaud P.O., Thiruvananthapuram-14,

Tele Fax No : 0471-2945647

0471-2945600, 0471-2945646

Email id : projects@kmscl.kerala.gov.in

CIN-U24233KL2007SGC021616

GSTIN:- 32AADCK4029M1ZK



Projects

KMSCL/Projects/1018/2016

www.kmscl.kerala.gov.in

Date: 20/02/2021

Notice Inviting RE-Quotation(NIQ)

Quotation No. RE-Quot/11/2020-2021

Sealed quotations are invited for Partition works for Waiting area at Karunya Community Pharmacy, Govt. Victoria Hospital compound, Kollam.

The envelopes containing the quotation should bear the superscription "Quotation No.KMSCL/Projects/RE-Quot/11/2020-2021,dated 20/02/2021, For The name of the bidder with contact address and phone number shall also be written on the cover and should be addressed to The Managing Director,Kerala Medical Services Corporation Limited,Thycaud P.O,Thiruvananthapuram-14.**Last date for receipt of quotations is 2/03/2021, at 3.30 pm.**Late quotations will not be accepted.

1) **The quotations will be opened at KMSCL Head Office,Thycaud on 2/03/2021 at 4.00 pm** in the presence of such of the bidders or their authorized representatives who may be present at that time. The details of work mentioned in the quotation document.

Details of the requirements and quotation document and the conditions governing their supply/work can be obtained free on request from tender/quotation inviting authority ,Kerala Medical Services Corporation Limited,Thycaud,Thiruvananthapuram and our website www.kmscl.kerala.gov.in

Sd/-

Managing Director

KMSCL

Place: Thiruvananthapuram

Date: 20/02/2021



KERALA MEDICAL SERVICES CORPORATION LIMITED

(Dept. of Health & Family Welfare, Govt. of Kerala)

Thycaud P.O, Thiruvananthapuram,

Kerala - 695 014

Partition works for waiting area for Karunya Community Pharmacy at
Govt.Victoria Hospital Compound,Kollam.

Quotation No.RE-Quot/11/2020-2021

Name:

Address

Signature

Last date and time for the receipt of quotation: 2.03.2021, 3.30 pm

Date of opening quotation bid: : 2.03.2021, 4.00 pm

NOT TRANSFERABLE

For details;

www.kmscl.kerala.gov.in

e-mail: **projects@kmscl.kerala.gov.in**

SECTION I

INTRODUCTION

1.The Kerala Medical Services Corporation Limited - KMSCL (Tender Inviting Authority) is a fully owned Government of Kerala company set up in 2007 for providing services to the various health care institutions under the Department of Health and Family Welfare. One of the key objectives of the KMSCL is to act as the central procurement agency for all essential drugs and equipments for all health care institutions (hereinafter referred to as user institutions) under the department.

2.The scope of work is Partition works for waiting area at Karunya Community Pharmacy, Govt.Victoria Hospital Compound,Kollam.

3.Every paise spend by the Corporation is public money and hence accountable.Therefore,each and every contractor guarantee to all the works under this tender/quotation and the performance of the works by the Corporation have to be given paramount importanace.

Looking forward for a long standing relation with you.

Best wishes,

Date: 20/02/2021

Sd/-

Managing Director , KMSCL

& Tender /Quotation Inviting Authority

SECTION II
SPECIAL CONDITIONS

- 1.The location of work is noted in the schedule.The contractor has to visit site before quoting the rate and interact with our representatives or Engineer and study all the requirements.
- 2.The quantities provided in the estimate are reasonably correct as per the assessment made.On actual execution,the quantities may vary by increasing or decreasing to the actual requirement.The contractor is liable to execute the work to the actual requirements of quantities.
- 3.The contractor has to provide all materials for the execution.Corporation does not take responsibility of supplying any material.The rate quoted shall be including all costs.
- 4.All materials before being incorporated in the work shall be inspected and if necessary tested before approval by the authorities.Any work on which such materials are used without prior inspection and without approval is liable to be considered as objective and not acceptable.
- 5.Works shall be carried out without disturbing the existing tiled/finished surface.
- 6.Any defects occurs on the existing surface will be replaced the contractor at his own cost.
- 7.The quotations shall be submitted in a single sealed cover with the superscription “Quotation No.KMSCL/Projects/RE-Quot/11/2020-2021, dated 20/02/21, For Partition works for Waiting area at KCP,Govt.Victoria Hospital Compound,Kollam.The name of the bidder with contact address and phone number shall also be written on the cover.
- 8.The sealed cover,shall be submitted in favour of “The Managing Director,Kerala Medical Services Corporation Limited,Thycaud P.O,Thiruvananthapuram-14.
- 9.The last date and time of submission of Quotations shall be 2/03/2021,3.30 pm.The quotations shall be sent by registered post or by courier or dropped in a box specifically kept at the KMSCL,Head Office,Thycaud,Thiruvananthapuram-14.The quotations obtained at the KMSCL,Head office shall be opened at 4.00 pm on the same day in the presence of the contractor or their representative,who choose to be present,at that time.The L1 list will be announced and published on the same day.

11.The agreement has to be executed by the L1 bidder in the prescribed form on stamp paper of value Rs.200/-purchased in the Kerala State.

12.The time of completion for the entire work is 21 days.Rate quotted should be inclusive of all taxes.

13.Quality of materials should be got approved from the quotation/tender inviting authority before supply of materials.

14.The contractor should co-operate with other contractors working at the site.

15.Time is the essence of the contract.The total work has to be completed in 21 days time.Commencement of the work shall be considered from the 1st day of receipt of work order or date of handing over of hindrance free site from client.

16.The work has to be completed and handed over by the end of 21 days from the date of commencement of work as per above conditions.If the contractor fails to complete and hand over the building within the specified period,the penalty shall be changed at 0.5% of the contract amount per week of delay till it is handed over or till the penalty reaches 10% of the contract amount,after which the work order stand cancelled and the balance work will be arranged at the risk and cost of the contractor.

17.SCHEDULE OF PAYMENTS

- a) 95% of the payment will be released within 2 weeks from the date of submission of detailed bill as per the actual quantities executed at the site.
- b) Balance 5% will be released after defect liability period of 6 months for observation of works.

Date: 20/02/2021

Sd/-
Managing Director,KMSCL
& Tender/Quotation Inviting Authority

I/We hereby declare that I/We have read and understood the above instructions and the terms and conditions mentioned above are binding on me/us.

Signature of the bidder

SCHEDULE OF QUANTITIES

	Description	Quantity	Unit	Rate	Amount
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron)	109.5	Kg		

2	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item):With float glass panes of 4.0 mm thickness.	8.75	Sqm		
3	Providing and fixing Pre - laminated medium density fibre board exterior grade (Grade-I) IS:14587:1998 marked, to frame, backing or studding with screws etc. complete (Frames, backing or studding to be paid separately). Pre-laminated with decorative lamination on both side exterior Grade - I MDF Board 12 mm thick confirming to IS:14587	2	Sqm		
4	Providing and fixing aluminium tubular handle bar 32 mm outer dia, 3.0mm thick & 2100 mm long with S.S. screws etc. complete as per direction of Engineer -in-Charge. Powder coated minimum thickness 50 micron aluminium tubular handle bar				
	Doors	2	Each		

5	Providing and fixing aluminium tower bolts, ISI marked, anodised(anodic coating not less than grade AC 10 as per : 1868), transparent or dyed to required colour or shade, with necessary screws complete: 250x10 mm	8	Each		
6	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width form 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete.	2	Each		
7	Providing and fixing 100 mm brass locks (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete	2	Each		

8	<p>Providing and fixing partition upto ceiling height consisting of G.I. frame and required board, including providing and fix]</p> <p>ing of frame work made of special section power pressed/ roll form G.I. sheet with Zinc coating of 120 gms/ (both side inclusive), consisting of floor and ceiling channel 50 mm wide having equal flanges of 32 mm and 0.50 mm thick, fixed to the floor and ceiling at the spacing of 610 mm centre to centre with dash fastener of 12.5 mm dia meter 50 mm length or suitable anchor fastener or metal screws with nylon plugs and the studs 48 mm wide having one flange of 34 mm and other flange 36 mm and 0.50 mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610 mm centre to centre by 6 mm dia bolts and nuts, including fixing of studs along both ends of partition fixed flush to wall with suitable anchor fastener or metal screws with nylon plugs at spacing of 450 mm centre to centre, and fixing of boards to both side of frame work by 25 mm long dry wall screws on studs, floor</p>	35.05	Sqm		
---	--	-------	-----	--	--

	<p>and ceiling channels at the spacing of 300 mm centre to centre. The boards are to be fixed to the frame work with joints staggered to avoid through cracks, M.S. fixing channel of 99 mm width (0.9 mm thick having two flanges of 9.5 mm each) to be provided at the horizontal joints of two boards, fixed to the studs using metal to metal flat head screws, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, angle beads at corners (25 mm x 25 mm x0.5 mm), joint finisher and two coats of primer suitable for board as per manufacture's specification and direction of engineer in charge all complete.</p> <p>66 mm overall thickness partition using 8 mm thick double skin non - asbestos multipurpose cement board reinforced with cellulose fibre manufactured through autoclaving process (High pressure steam cured) as per IS : 14862 with suitable fibre cement screws</p>				
	TOTAL				

Total Amount(in words).....(inclusive of all taxes)

Date:

Signature of the bidder