



KERALA MEDICAL SERVICES CORPORATION LIMITED

(Dept. of Health & Family Welfare, Govt. of Kerala)

Thycaud P.O, Thiruvananthapuram,

Kerala - 695 014

Quotation No. Quo/006/2022-23

Providing & installing sliding gate work at KMSCL Head
Office, Thycaud, Thiruvananthapuram.

Name:

Address

Signature

Last date and time for the receipt of quotation : 13/05/2022, 4.30 pm

Date of opening quotation bid: : 16/05/2022, 11.00 am

NOT TRANSFERABLE

For details;

www.kmscl.kerala.gov.in

e-mail: **projects@kmscl.kerala.gov.in**

SECTION I

INTRODUCTION

1.The Kerala Medical Services Corporation Limited - KMSCL (Tender Inviting Authority) is a fully owned Government of Kerala company set up in 2007 for providing services to the various health care institutions under the Department of Health and Family Welfare. One of the key objectives of the KMSCL is to act as the central procurement agency for all essential drugs and equipments for all health care institutions (hereinafter referred to as user institutions) under the department.

2.The scope of work is Providing and installing Sliding gate work at KMSCL Head Office,Thycaud,Thiruvananthapuram.

3.Every paise spend by the Corporation is public money and hence accountable.Therefore,each and every contractor guarantee to all the works under this tender/quotation and the performance of the works by the Corporation have to be given paramount importanace.

Looking forward for a long standing relation with you.

Best wishes,

Date: 6 /05/2022

Sd/-
Managing Director , KMSCL

& Tender /Quotation Inviting Authority

SECTION II
SPECIAL CONDITIONS

- 1.The location of work is noted in the schedule.The contractor has to visit site before quoting the rate and interact with our representatives or Engineer and study all the requirements.
- 2.The quantities provided in the estimate are reasonably correct as per the assessment made.On actual execution,the quantities may vary by increasing or decreasing to the actual requirement.The contractor is liable to execute the work to the actual requirements of quantities.
- 3.The contractor has to provide all materials for the execution.Corporation does not take responsibility of supplying any material.The rate quoted shall be including all costs.
- 4.All materials before being incorporated in the work shall be inspected and if necessary tested before approval by the authorities.Any work on which such materials are used without prior inspection and without approval is liable to be considered as objective and not acceptable.
- 5.Works shall be carried out without disturbing the existing tiled/finished surface.
- 6.Any defects occurs on the existing surface will be replaced the contractor at his own cost.
- 7.The quotations shall be submitted in a single sealed cover with the superscription “Quotation No.KMSCL/Projects/Quo/006/2022-2023, dated 6/05/22,For Providing and installing Sliding gate work at KMSCL Head Office,Thycaud,Thiruvananthapuram.
The name of the bidder with contact address and phone number shall also be written on the cover.
- 8.The sealed cover,shall be submitted in favour of “The Managing Director,Kerala Medical Services Corporation Limited,Thycaud P.O,Thiruvananthapuram-14.
- 9.The last date and time of submission of Quotations shall be 13/05/2022,4.30 pm.The quotations shall be sent by registered post or by courier or dropped in a box specifically kept at the KMSCL,Head Office,Thycaud,Thiruvananthapuram-14.The quotations obtained at the KMSCL,Head office shall be opened on 16/05/22 @11.00 am in the presence of the contractor or the contractor or their representative,who choose to be present,at that time.
The L1 list will be announced and published on the same day.

10. The agreement has to be executed by the L1 bidder in the prescribed form on stamp paper of value Rs.200/-purchased in the Kerala State.

11. The time of completion for the entire work is 15 days.Rate quotted should be inclusive of all taxes.

12. Quality of materials should be got approved from the quotation/tender inviting authority before supply of materials.

13. The contractor should co-operate with other contractors working at the site.

14. Time is the essence of the contract.The total work has to be completed in 15 days time.Commencement of the work shall be considered from the 1st day of receipt of work order or date of handing over of hindrance free site from client.

15. The work has to be completed and handed over by the end of 15 days from the date of commencement of work as per above conditions.If the contractor fails to complete and hand over the building within the specified period,the penalty shall be charged at 0.5% of the contract amount per week of delay till it is handed over or till the penalty reaches 10% of the contract amount,after which the work order stand cancelled and the balance work will be arranged at the risk and cost of the contractor.

16. SCHEDULE OF PAYMENTS:

- a) 95% of the payment will be released within 2 weeks from the date of submission of detailed bill as per the actual quantities executed at the site.
- b) Balance 5% will be released after defect liability period of 6 months for observation of works.

Sd/-

Date: 6/05/2022

**Managing Director,KMSCL
& Tender/Quotation Inviting Authority**

I/We hereby declare that I/We have read and understood the above instructions and the terms and conditions mentioned above are binding on me/us.

Signature of the bidder

SCHEDULE OF QUANTITIES

	Description	Quantity	Unit	Rate	Amount
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	9	<i>sqm</i>		
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil	0.21	Cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	0.05	Sqm		
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:	33.4	<i>Sqm</i>		

	Two or more coats on new work				
5	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	473	Kg		
	TOTAL				

Total Amount(in words)(inclusive of all taxes)

Date:

Signature of the bidder