



## KERALA MEDICAL SERVICES CORPORATION LTD

(A Government Of Kerala Undertaking)

Thycaud.P.O., Thiruvananthapuram-14.

Tele Fax No. 0471-2945647

0471-2945646, 0471-2945600

E-mail id : [elec.kmscl@kerala.gov.in](mailto:elec.kmscl@kerala.gov.in)

CIN : U24233KL2007SGC021616

GSTIN: 32AADCK4029M1ZK

No: KMSCL/PROJECTS/278/2016

Dated: 06.08.2026

Projects Division

[www.kmscl.kerala.gov.in](http://www.kmscl.kerala.gov.in)

### Notice Inviting Quotation (N.I.Q)

(Quotation No: QUOT-KMSCL/Projects/Quot no 38/2026/R)

#### Sealed quotations are invited for Electrification of 40kVA DG set at KINFRA KMSCL DDWH Thiruvananthapuram

Notice Inviting Quotation (Re-NIQ) for the Electrification of 40KVA DG set at KINFRA,KMSCL DDWH Thiruvananthapuram on behalf of Kerala Medical Services Corporation Ltd. (KMSCL) from Eligible electrical contractors/registered bidders of Kerala PWD, CPWD, other Central or State Government Departments, State or Central Public Sector Undertakings, etc., having experience in similar electrical works, as well as OEMs of DG sets or their authorized service providers, may participate in the quotation. All other details are available in website [www.kmscl.kerala.gov.in](http://www.kmscl.kerala.gov.in)

#### Details

| SL No | Name of Work                                                               | Quot No                           | Estimate Amount(Apprx) incl of taxes(Rs) | Last Date of submission |
|-------|----------------------------------------------------------------------------|-----------------------------------|------------------------------------------|-------------------------|
| 01.   | Electrification for 40 kVA DG set at KINFRA,KMSCL DDWH, Thiruvananthapuram | Quot no- KMSCL/Projects/38/2026/R | 97,235/-                                 | 18/08/2026              |

Yours faithfully

**Dr Arun P V**

General Manager

Encl:-Quotation document



## KERALA MEDICAL SERVICES CORPORATION LIMITED

*(Dept. of Health & Family Welfare, Govt. of Kerala)*

Thycaud P.O, Thiruvananthapuram,

Kerala - 695 014

**Electrification work for 40 kVA DG Set at KINFRA KMSCL DDWH Warehouse,TVM**

**Quotation No-KMSCL/PROJECTS/38/2026/R**

Name:

Address

Signature

Last date and time for the receipt of quotation: 18.08.26 03.00 .P.M

Date of opening quotation bid : 18 .08.26 04.00 P.M

NOT TRANSFERABLE

*For details;*

e-mail: [elec.kmscl@kerala.gov.in](mailto:elec.kmscl@kerala.gov.in)

## **SECTION I**

### **INTRODUCTION**

1.The Kerala Medical Services Corporation Limited - KMSCL (Quotation Inviting Authority) is a fully owned Government of Kerala company set up in 2007 for providing services to the various health care institutions under the Department of Health and Family Welfare. One of the key objectives of the KMSCL is to act as the central procurement agency for all essential drugs and equipment's for all health care institutions (hereinafter referred to as user institutions) under the department.

2.The scope of work is Electrification work for 40kVA DG Set at KINFRA district drug Warehouse, Thiruvananthapuram.

3.KMSCL has installed DG sets of Various Ratings for providing interruption free power supply to the Drug Warehouses, Karunya Pharmacy Outlets and its Depot's, Govt. Hospitals etc throughout the state. The DG sets after warranty period were maintained through Engine Manufacturer /Authorized Dealers of its Engine manufacturer available in the state who can provide better service and attend the breakdowns in a short span of time

4.Every paise spend by the Corporation is public money and hence accountable. Therefore, each and every contractor guarantee to all the works under this tender/quotation and the performance of the works by the Corporation have to be given paramount importance.

Looking forward for a long standing relation with you.

Best wishes,

Date: 06/08/2026

**Managing Director ,KMSCL  
&Quotation Inviting Authority**

## Kmscl invites Sealed quotations from OEM/Authorized Service providers

| SL No | Name of Work                                                      | Quot No                  | Estimate Amount(Ap prx) incl of taxes(Rs) | Last Date of submission |
|-------|-------------------------------------------------------------------|--------------------------|-------------------------------------------|-------------------------|
| 01.   | Electrification work for 40 kVA DG set at KINFRA,DDWH,Triv andrum | KMSCL/PROJECTS/38/2026/R | 97,234/-                                  | 18/08/2026<br>@4.00pm   |

## SECTION II

### SPECIAL CONDITIONS

1. The location of work is as noted in the schedule. The contractor has to visit site before quoting the rate and interact with our representatives or Engineer and study all the requirements.
2. The quantities provided in the estimate are reasonably correct as per the assessment made. On actual execution, the quantities may vary by increasing or decreasing to the actual requirement. The contractor is liable to execute the work to the actual requirements of quantities.
3. The contractor has to provide all materials for the execution. Corporation does not take responsibility of supplying any material/tools. The rate shall be quoted inclusive of all charges(Material/tools).
4. All materials before being incorporated in the work shall be inspected and if necessary tested before approval by the authorities. Any work on which such materials are used without prior inspection and without approval is liable to be considered as rejected and treated as unacceptable.
5. KMSCL invites Sealed quotations with Two Cover system (Cover I Prequalification cum Technical Bid Document, Cover II Commercial bid) are invited for the following work from Eligible contractors /Registered Bidders of Kerala PWD/Central PWD/Other Central or State Government Departments/State or Central Public Sector Undertakings etc having experience in electrical works may participate.
6. Cover 1 – Copy of GST Certificate, Copy of PAN Card , Copy of License  
Cover 2 - Commercial bid (Section III : Schedule of quantity).
7. The quotations shall be submitted in a single sealed cover with the superscription **“Quotation No.KMSCL/Projects/38/2026/R ,dated: 06/08/26,”** Electrification works of 40kVA DG Set at KINFRA district drug warehouse,Thiruvananthapuram.
8. The name of the bidder with contact address and phone number shall also be written on the cover.
9. The sealed cover, shall be submitted in favour of “The Managing Director, Kerala Medical Services Corporation Limited, Thycaud P.O,Thiruvananthapuram-14.
10. Electric power for the work has to be arranged by the contractor
11. Quality of materials should be got approved from the quotation/tender inviting authority before supply of materials.
12. Time is the essence of the contract. The total work has to be completed in 30 days time. Commencement of the work shall be considered from the 1st day of receipt of work order.
13. The work has to be completed and handed over by the end of 30 days from the date of commencement of work as per above conditions. If the contractor fails to complete and hand over the DG electrification work within the specified period, the penalty shall be charged at 0.5% of the contract amount per week of delay till it is handed over or till the

penalty reaches 5% of the contract/value of executed amount, after which the work order stand cancelled and the balance work will be arranged at the risk and cost of the contractor.

14. The bidder shall have valid GST Registration number. GST as applicable for the work will be paid extra by the KMSCL. The GST applicable as per law can be billed to the KMSCL, which will be paid to the bidder by the KMSCL along with the bills, for which the bidder shall hold valid GST Registration number.
15. Defects Liability Period: The defects liability period for the DG electrification work shall be 12 months from the date of completion and commissioning of the work. Any defect or deficiency noticed during this period due to defective materials, workmanship, installation, or design shall be rectified by the contractor at his own cost.
16. The work shall be completed without causing any damage to the existing structures/cables etc. In case any damage is caused, the same has to be rectified at Quotationer's risk and cost.
17. The last date and time of submission of Quotations shall be **18/08/2026 03.00PM**. The quotations shall be sent by registered post or by courier or dropped in a box specifically kept at the KMSCL, Head Office, Thycaud, Thiruvananthapuram-14. The quotations obtained at the KMSCL, Head office shall be opened at 04.00PM on the same day in the presence of the contractor or their representative, who choose to be present, at that time. The L1 list will be announced and published on the same day.
18. The contractor shall be responsible for carrying out complete testing and commissioning of the DG set, changeover arrangement, power and control cables, earthing system and associated accessories to the satisfaction of the Engineer-in-Charge.
19. The contractor shall ensure proper termination, glanding, ferruling, identification and dressing of all power and control cables. All cable terminations shall be carried out using suitable glands and lugs of approved make.
20. The contractor shall ensure proper earthing of the DG set, neutral, AMF panel, cable armour, and all metallic parts as per applicable standards and statutory requirements.
21. Necessary insulation resistance tests, continuity tests, earth resistance tests, phase sequence checks, voltage and frequency checks and load tests shall be conducted before commissioning. Test reports shall be submitted to KMSCL.
22. The quoted rate shall be inclusive of supply, transportation, installation, testing, commissioning, labour charges, tools and tackles, and all incidental expenses required for satisfactory completion of the work

#### **15. SCHEDULE OF PAYMENTS**

Payment Terms & schedule: - 95% of the Payment shall be paid after completion of the work on submitting the original Invoices and service reports duly signed by the Warehouse Managers/Depot-In Charge and balance 5% will be released after six months of defect liability.

Date: <sup>06</sup> /08/2026

**Sd/-**  
**Managing Director, KMSCL**  
**& Tender/Quotation Inviting Authority**

I/We hereby declare that I/We have read and understood the above instructions and the terms and conditions mentioned above are binding on me/us.

**Signature, seal & Address of the bidder**

### SECTION III

#### SCHEDULE OF QUANTITIES

| SL NO | Description                                                                                                                                                                                                                                                           | Quantity | Unit  | Rate | Amount |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|------|--------|
| 1     | Supply and laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.Upto 35 sq. mm (3.5x35sq.mm) | 40       | meter |      |        |
| 2     | Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required 3.5X 35 sq. mm (32mm)                                          | 4        | set   |      |        |
| 3     | Supply and Laying of fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required.Upto 35 sq. mm (clamped with 1mm thick saddle)                                                              | 20       | meter |      |        |
| 4     | Supply, installation, testing and commissioning of earthing system comprising GI pipe electrode (40 mm dia, 3/4.5 m long) with                                                                                                                                        | 3        | no    |      |        |

|   |                                                                                                                                                                                                                                                                                                                                                 |    |       |  |  |
|---|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-------|--|--|
|   | chemical earthing compound backfill, including excavation in all types of soil, refilling, masonry chamber with cover, and watering arrangement. Providing and laying 25 mm × 5 mm GI strip/wire as earthing conductor from electrode to equipment, laid in trenches/pipe/on wall as required, complete in all respects, conforming to IS 3043. |    |       |  |  |
| 5 | Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required 3.15 mm copper conductor ( 10 SWG)                                                                                                                                                                               | 20 | meter |  |  |
| 6 | Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required 6.00 mm copper conductor (4 SWG)                                                                                                                                                                                 | 35 | meter |  |  |
| 7 | Supply of superior quality copper earth socket for the following size of earth conductor including crimping etc. as required 6. mm ( 4 SWG)                                                                                                                                                                                                     | 20 | meter |  |  |
| 8 | Supply of superior quality copper earth socket for the following size of earth conductor including crimping etc. as required 3.15 mm (10 SWG)                                                                                                                                                                                                   | 10 | meter |  |  |
| 9 | Supply and drawing of 16 sq.mm PVC insulated copper flexible wire through existing PVC conduit, including                                                                                                                                                                                                                                       | 16 | meter |  |  |

|    |                                                                                                                                                                                                                                                     |   |      |  |  |
|----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|------|--|--|
|    | clamping, routing, and making connections with all accessories as required                                                                                                                                                                          |   |      |  |  |
| 10 | Supply of superior quality copper tubular cable socket and making core termination of cables of the following sizes including crimping etc. as required.16 sq mm                                                                                    | 4 | each |  |  |
| 11 | Supply, installation, testing and commissioning of 125 Amps, 4-pole changeover switch with suitable sheet steel enclosure, including fixing, cable termination, interconnections, earthing, and all necessary accessories, complete in all respects | 1 | no   |  |  |
| 12 | Shifting of DG set                                                                                                                                                                                                                                  | 1 | job  |  |  |
|    | <b>Total Amount</b>                                                                                                                                                                                                                                 |   |      |  |  |
|    | <b>GST@18%</b>                                                                                                                                                                                                                                      |   |      |  |  |
|    | <b>Grand Total</b>                                                                                                                                                                                                                                  |   |      |  |  |
|    | <b>Quoted rate(inclusive of all charges)</b>                                                                                                                                                                                                        |   |      |  |  |