



KERALA MEDICAL SERVICES CORPORATION LTD

(A Government Of Kerala Undertaking)

Thycaud.P.O., Thiruvananthapuram-14.

Tele Fax No. 0471-2945647

0471-2945646, 0471-2945600

E-mail id : civil.kmscl@kerala.gov.in

CIN : U24233KL2007SGC021616

GSTIN: 32AADCK4029M1ZK

No: KMSCL/PROJECTS/30/2025

Dated: 06.10.2025

Projects Division

www.kmscl.kerala.gov.in

Notice Inviting Quotation (N.I.Q)

(Quotation No: QUOT-KMSCL/Projects/65/2025.)

Sealed Quotations are invited for the Electrification works for new KCP store and the 2nd outlet at Medical College Hospital, Thiruvananthapuram.

The envelopes containing the quotation should bear the superscript on Quotation No.KMSCL/Projects/Quot/65/2025 dated 06/10/2025, The name of the bidder with contact address and phone number shall also be written on the cover and should be addressed to The Managing Director, Kerala Medical Services Corporation Limited, Thycaud P.O., Thiruvananthapuram-14. Last date for receipt of quotations is 09/10/2025, at 12.30 pm. Late quotations will not be accepted.

The quotations will be opened at KMSCL Head Office, Thycaud on 09/10/2025 at 02.30 pm in the presence of such of the bidders or their authorised representatives who may be present at that time. The maximum period required for delivery of the articles mentioned in the quotation document.

Details of the requirements and quotation document, and the conditions governing their supply/work details can be obtained free on request from the tender/quotation inviting authority, Kerala Medical Services Corporation Limited, Thycaud, Thiruvananthapuram and the KMSCL website. www.kmscl.kerala.gov.in till 09/10/2025@ 12.30 pm.

Yours faithfully

Dr Arun P V
General Manager



KERALA MEDICAL SERVICES CORPORATION LIMITED

(Dept. of Health & Family Welfare, Govt. of Kerala)

Thycaud P.O, Thiruvananthapuram,

Kerala - 695 014

Quotation No-KMSCL/Projects/65/2025

**Electrification works for new KCP Store and 2nd outlet at
MCH,Thiruvananthapuram.**

Name:

Address

Signature

Last date and time for the receipt of quotation: 09/10/2025@12.30pm

Date of opening quotation bid: 09 /10/2025@2.30pm:

NOT TRANSFERABLE

For details;

Website address: www.kmscl.kerala.gov.in

SECTION I

INTRODUCTION

- 1.The Kerala Medical Services Corporation Limited - KMSCL (Tender Inviting Authority) is a fully owned Government of Kerala company set up in 2007 for providing services to the various health care institutions under the Department of Health and Family Welfare. One of the key objectives of the KMSCL is to act as the central procurement agency for all essential drugs and equipments for all health care institutions (hereinafter referred to as user institutions) under the department.
- 2.The scope of work is Electrification works for new KCP Store and 2nd outlet at MCH, Thiruvananthapuram.
3. Every paisa spend by the Corporation is public money and hence accountable Therefore, each and every contractor guarantee to all the works under this tender/quotation and the performance of the works by the Corporation have to be given paramount importance.

Looking forward for a long standing relation with you.

Best wishes,

Date. 06/10/2025

Sd/-
Managing Director, KMSCL
& Tender /Quotation Inviting Authority

SECTION II

SPECIAL CONDITIONS

1. The location of work is as noted in the schedule. The contractor has to visit site before quoting the rate and interact with our representatives or Engineer and study all the requirements.
2. The quantities provided in the estimate are reasonably correct as per the assessment made. On actual execution, the quantities may vary by increasing or decreasing to the actual requirement. The contractor is liable to execute the work to the actual requirements of quantities.
3. The contractor has to provide all materials for the execution. Corporation does not take responsibility of supplying any material/tools. The rate shall be quoted inclusive of all charges. Material/ tools. The rate shall be quoted inclusive of all charges. Material/tools. The rate shall be quoted inclusive of all charges.
4. All materials before being incorporated in the work shall be inspected and if necessary tested before approval by the authorities. Any work on which such materials are used without prior inspection and without approval is liable to be considered as objectionable and not acceptable.
5. KMSCL invites Sealed quotations with Two Cover system (Cover I Prequalification cum Technical Bid Document, Cover II Commercial bid) are invited for the following work from Eligible contractors /Registered Bidders of Kerala PWD/Central PWD/Other Central or State Government Departments/State or Central Public Sector Undertakings etc
6. Cover 1 – Copy of GST Certificate, Copy of PAN Card , Copy of License
Cover 2 - Commercial bid (Section I V : Schedule of quantity)
7. The quotations shall be submitted in a single sealed cover with the superscription
"Quotation No.KMSCL/Projects/65/2025 ,dated: 06/10/25," Electrification works for new KCP Store and 2nd outlet at MCH, Thiruvananthapuram
8. The name of the bidder with contact address and phone number shall also be written on the cover.
9. The sealed cover, shall be submitted in favour of "The Managing Director, Kerala Medical Services Corporation Limited, Thycaud P.O, Thiruvananthapuram-14.

10. The last date and time of submission of Quotations shall be 09/10/2025@ 12.30pm. The quotation documents and NIQ available in KMSCL website- The quotations shall be sent by registered post or by courier or dropped in a box specifically kept at the KMSCL, Head Office, Thycaud, Thiruvananthapuram-14. The quotations obtained at the KMSCL, Head office shall be opened at 09/10/2025 @ 02.30 pm in the presence of the contractor or their representative, who choose to be present, at that time. The L1 list will be announced and published on the same day.

11. Electric power for the work has to be arranged by the contractor

12. The time of completion for the entire work is 3 days. Rate quoted should be inclusive of all taxes.

13. Quality of materials should be got approved from the quotation/tender inviting authority before supply of materials.

14. Time is the essence of the contract. The total work has to be completed in 03 days time. Commencement of the work shall be considered from the 1st day of receipt of work order.

15. The work has to be completed and handed over by the end of 03 days from the date of commencement of work as per above conditions. If the contractor fails to complete and hand over the building within the specified period, the penalty shall be charged at 0.5% of the contract amount per week of delay till it is handed over or till the penalty reaches 5% of the contract/value of executed amount, after which the work order stand cancelled and the balance work will be arranged at the risk and cost of the contractor.

16. The Quotationer shall have valid GST Registration number. GST as applicable for the work will be paid extra by the KMSCL. The GST applicable as per law can be billed to the KMSCL, which will be paid to the Quotationer by the KMSCL along with the bills, for which the Quotationer shall hold valid GST Registration number

17. Defects Liability Period: The defects liability period for the work shall be 6 months from the date of completion of the work. In the event of any defect/ deficiency being noticed during the period, which is attributable to the defective materials/design/ workmanship, the Quotation shall make good the same at his cost.

18. The work shall be completed without causing any damage to the existing structures/cables etc. In case any damage is caused, the same has to be rectified at Quotationer's risk and cost.

19. SCHEDULE OF PAYMENTS

- a) 95% of the payment shall be released after completion of the work. Balance 5 % will be released after liability period 6 months of verification of work.

Date: 06 /10/2025

Sd/-
Managing Director, KMSCL
& Tender/Quotation Inviting Authority

I/We hereby declare that I/We have read and understood the above instructions and the terms and conditions mentioned above are binding on me/us.

Signature of the bidder

SECTION III

SCHEDULE OF QUANTITIES

| Sl.no | Description | Quantity | Unit | Rate | Amount |
|-------|--|----------|-------|------|--------|
| 1 | 1.10.3 : Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required Group C | 10 | each | | |
| 2 | 1.14.1 : Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required 2x1.5 sq.mm + 1x1.5 sq.mm earth wire | 50 | metre | | |
| 3 | 1.14.2 : Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required 2X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire | 30 | metre | | |
| 4 | 1.14.3 : Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required 2 X 4 sq. mm + 1 X 4 sq. mm earth wire | 30 | metre | | |
| 5 | 1.17.3 : Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required. 3 X 1.5 sq.mm | 30 | metre | | |
| 6 | 1.17.12 : Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required. 3 x 2.5 sq. mm | 30 | metre | | |
| 7 | 1.21.1 : Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required. 20 mm | 10 | metre | | |
| 8 | 1.21.2 : Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required. 25 mm | 15 | metre | | |
| 9 | 1.27.1 : Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required. 1 or 2 Module (75mmX75mm) | 8 | each | | |

| | | | | | |
|----|---|----|-------|--|--|
| 10 | 1.27.2 : Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.3 Module (100mmX75mm) | 4 | each | | |
| 11 | 1.27.4 : Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.6 Module (200mmX75mm) | 1 | each | | |
| 12 | 1.27.6 : Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.12 Module (200mmX150mm) | 2 | each | | |
| 13 | 1.24.1 : Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.5/6 amps switch | 12 | each | | |
| 14 | 1.24.3 : Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.15/16 amp switch | 7 | each | | |
| 15 | 1.24.4 : Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.3 pin 5/6 amp socket outlet | 12 | each | | |
| 16 | 1.24.5 : Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.6 pin 15/16 amp socket outlet | 7 | each | | |
| 17 | 1.28.1 : Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.1 or 2 Module | 8 | each | | |
| 18 | 1.28.2 : Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.3 Module | 4 | each | | |
| 19 | 1.28.4 : Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.6 Module | 1 | each | | |
| 20 | 1.28.6 : Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.12 Module | 2 | each | | |
| 21 | Supply & fixing 20W LED Cool White/White Type Tube light ,Light Fittings Philips/Havells/Similar superior make | 8 | each | | |
| 22 | 2.15.3 Supplying and fixing following rating, four pole, (three phase and neutral), 415 volts, residual current circuit breaker (RCCB), having a sensitivity current upto 300 milliamperes in the existing MCB DB complete with connections, testing and commissioning etc. as required.63 amps | 1 | each | | |
| 23 | 1.17.31 Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required. 4 x 6 sq. mm | 20 | metre | | |

| | | | | | |
|----|--|----|------|--|--|
| 24 | 2.23.1 Supplying and fixing Cable End Box (Loose Wire Box) (IP 43) suitable for following single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with testing and commissioning etc. as required. 2 For 6 way, Double door SPN MCBDB | 1 | each | | |
| 25 | 90.11.1.10 Supply and installation of sheet steel, phosphatised and painted, dust and vermin proof enclosure of MCB DB including copper /brass bus bar, neutral link, earth bus and DIN rail suitable for fixing MCB/ isolator etc. fixed on wall using suitable anchor bolts or fixed in recess including cutting hole on the wall , making good the damages, colour washing etc. as required 4 way (8+12) - three phase double cover (IP 42/43) | 1 | each | | |
| 26 | 2.10.1 : Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required Single pole | 14 | each | | |
| 27 | 2.12.2 : Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.40 amps | 1 | each | | |
| 28 | 2.13.2 Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63 Amps | 1 | each | | |
| 29 | dismantling old wiring & pipes | 1 | job | | |
| | Total amount | | | | |
| | GST@18% | | | | |
| | Grand Total | | | | |
| | Quoted rate(inclusive all charges) | | | | |

Signature of the bidder with seal