

Running Contract Details	
Equipment Name	Passbox (Dynamic)
Running Contract Valid Till	13-08-2028
Tender Ref No	KMSCL/EP/T570(R)/1712A/2025
Tendered Quantity	15
Supplier Name	M/s Labline Instruments
GST No	32AABFL5818N1Z6
Installation & Delivery Period	8 Week(s)
Up-time / PM vist	95% & 0 Visits per year
Warranty period	3 Years

Supplier`s Details		
Address	Contact Details	
P B No. 36 Eroor Road Trippunithura-682301	Contact Person	Bini
	Phone	04842776582
	Mobile No	9020304422
	Email	lablinecochin@gmail.com

Item-wise Price Details				
#	Item Details	Unit Rate (Incl.all taxes & charges)	Service Charges (Through KMSCL)	Grand Total
1	Passbox (Dynamic) <i>Model & Make : LDPB- 2/ Labline Instruments</i>	140892 Incl.GST :18%	9862.44	150754.44
		140892	9862.44	150754.44

Other terms & conditions

1. The supplier shall execute an agreement with the purchaser as per tender conditions (agreement format is given in the tender document).
2. The supplier shall submit performance security amounting to 5.00% of the value of the supply order.
3. The labour & comprehensive charges of equipment after the completion of warranty period is finalized by KMSCL as mentioned above.
4. Since discount rate is not applicable for equipment under Running Contract of KMSCL, purchase/supply order can be issued directly to supplier at the given rate with tax & other charges (exclusive of KMSCL service charges).

5. If purchase/supply order is issued directly to the supplier, KMSCL service charge need not be paid. But the copy of the said order may be forwarded to KMSCL for information.

Technical Specification

Equipment :Passbox (Dynamic)

1. Should have Stainless steel with HEPA filter
2. Should have dimension minimum 600mm X 600mm X600mm
3. Should have two side doors with glass windows
4. Should have stainless steel handles and hinges
5. Should have Electromagnetic interlocking system
6. Should have Vertical airflow, Motor blower with speed controller
7. Power supply :220-240-v, 50/60 Hz
8. Should have UV light, light indicators for door
9. Should provide on and off switch for blower
10. Should have LED illumination light, analog / digital pressure gauge, door buzzer, UV light hour meter
11. Should have CE,ISO certified.